

Transmittals of Shop Drawings, Equipment Data, Material, Samples, Manufacturer's Certificates of Compliance for Review	Date:  1/24/2017	Transmittal Number:  5
---	------------------------	------------------------------


Section I (Contractor)			
TO: MELISSA HILBRAY General Services Administration 400 15th St Auburn WA 98001	From: Lummi Nation Construction Company 2665 Kwina RD Bellingham, WA 98226	Contract Number: GS-10-P-16-LT-D-7002/ GS-P-10-17-LT-0002	LNCC Job Number: 2
Project Name & Location: Sumas Kitchen Upgrade Land Port of Entry, 03 Cherry Street. Sumas, WA 98295			

Item No:	Description (include Brand Name or Manufacturer's Name)	Submittal Number	Spec Section	Contract Drawing Number	Action Code
1	whirlpool free standing electric range stove/oven	2	N/A	N/A	

Name & Signature of Contractor:	Contractor certifies he has reviewed the plans and specifications, the submittal is in accordance with the contract documents or deviations are clearly identified; individual product characteristics and assemblies have been coordinated with actual field conditions; systems are complete; system and system components can be installed and will function as intended.
AL TIMMER	

Section II (Reviewer)								
For review and comment								
Reviewed By:		Signature (Reviewer):		Date:				
Action Codes:		A- Approved		D- Rejected				
		B- Approved as Noted		E- Other _____				
		C- Approved as Noted; Rev & Resub.						

WHIRLPOOL® 5.3 CU. FT. FREESTANDING ELECTRIC RANGE WITH HIGH-HEAT SELF-CLEANING SYSTEM



## WFE530C0ES

Whirlpool® 5.3 Cu. Ft. Freestanding Electric Range with High-Heat Self-Cleaning System

### MAJOR APPLIANCE

[Email product details](#)

[Print Product Details](#)

### Specifications

### Product Literature

### Electrical Requirements

#### Available Colors

☒ **Black**  
Model: WFE530C0EB  
MAJOR APPLIANCE

☐ **Black-on-Stainless**  
Model: WFE530C0ES  
MAJOR APPLIANCE

☐ **White**  
Model: WFE530C0EW  
MAJOR APPLIANCE

US MADE

+ Larger View

AVAILABLE IMAGES 1



### Related Products




8009  
40 Watt Appliance Bulb



W10123240  
Premium Broil Pan & Roasting Rack



4396923  
Porcelain Broiler Pan & Grid



4378577  
Brick Baking Stone



8171385RC  
4' 3-Wire 40 amp Power C

### Dimensions

Height	47 7/8 Inches
Depth	27 3/4 Inches
Width	29 7/8 Inches
Gross Weight	150 LB

Dimensions shown are for planning purposes only. For complete information, see Installation Instructions packed with product.

### Specifications

### Cooktop Features

### Key Features


- Counter Depth Range [more](#)
- FlexHeat™ Dual Radiant Element [more](#)
- 5.3 Cu. Ft. Capacity
- Easy Wipe Ceramic Glass Cooktop [more](#)
- Temperature Sensor [more](#)
- EasyView™ Large Oven Window
- Hidden Bake Element [more](#)
- SteamClean Option [more](#)
- High-Heat Self-Cleaning System
- #1 Selling Appliance Brand in the U.S.A. [more](#)

Cooktop Element Style	Smoothtop
Cooktop Surface Color	Black
Cooktop Surface Material	Glass
Number of Cooking Element-Burners	5
Center Rear Element-Burner Power	100W
Center Rear Element-Burner Size	6"
Center Rear Element-Burner Type	Warming
Left Front Element-Burner Power	3000W
Left Front Element-Burner Size	12"/9"
Left Front Element-Burner Type	Dual
Left Rear Element-Burner Power	1200W
Left Rear Element-Burner Size	6"
Right Front Element-Burner Power	3000W
Right Front Element-Burner Size	9"/6"
Right Front Element-Burner Type	Dual
Right Rear Element-Burner Power	1200W
Right Rear Element-Burner Size	6"
<b>Oven Features</b>	
Number of Oven Lights	1
Hot Surface Indicator Light	Yes
Power On Indicator Light	Yes
Light Type	Incandescent
Oven Rack Type	Standard
<b>Controls</b>	
Drawer Type	Storage Drawer
Handle Material	Metal
Handle Type	Reach-Through Handle
Selections	Clock; Timer; Keep Warm Setting; Delay Start; Cook Time Indicator; Audible Signal; Sabbath Mode; Control Lock
<b>Dimensions</b>	
Depth	27 3/4 Inches
Height	47 7/8 Inches
Width	29 7/8 Inches

Product Literature

- [Owners Manual](#) (385.18 KB)
- [Dimension Guide](#) (87.55 KB)
- [Installation Instructions](#) (764.10 KB)
- [Warranty](#) (81.50 KB)

Email product details

You may need to install Adobe Acrobat Reader  to view these documents.

Electrical Requirements

40 AmpsAmps. 60Hz. 120/240V.

UPC Listing

Model "WFE530C0EB" UPC: 883049356006  
 Model "WFE530C0ES" UPC: 883049356013  
 Model "WFE530C0EW" UPC: 883049356020





## 30" (76.2 cm) Freestanding Electric Range

### PRODUCT MODEL NUMBERS

WFC110	WFE330	WFE540
WFC120	WFE510	WFE710
WFC130	WFE515	WFE714
WFC150	WFE520	WFE720
WFC310	WFE524	WFE745
WFC340	WFE525	WFE770
WFE320	WFE530	WFE905
		WFI910

**Electrical:** To properly install your range, you must determine the type of electrical connection you will be using and follow the instructions provided for it here.

■ Range must be connected to the proper electrical voltage and frequency as specified on the model/serial number rating plate. The model/serial number rating plate is located on the left-side frame behind the storage drawer panel or behind the top right side of the oven door. Refer to the figures in the "Product Dimensions" section of the "Location Requirements" section.

■ This range is manufactured with the neutral terminal connected to the cabinet. Use a 3-wire, UL Listed, 40- or 50-amp power supply cord (pigtail) (see following Range Rating chart). If local codes do not permit ground through the neutral, use a 4-wire power supply cord rated at 250 volts, 40 or 50 amps and investigated for use with ranges.

Range Rating*		Specified Rating of Power Supply Cord Kit and Circuit Protection
120/240 Volts	120/208 Volts	Amps
8.8 – 16.5 KW	7.8 – 12.5 KW	40 or 50 **
16.6 – 22.5 KW	12.6 – 18.5 KW	50

\*The NEC calculated load is less than the total connected load listed on the model/serial rating plate.

\*\* If connecting to a 50-amp circuit, use a 50-amp rated cord with a kit. For 50-amp rated cord kits, use kits that specify use with a nominal 1 $\frac{3}{8}$ " (34.9 mm) diameter connection opening.

■ A circuit breaker is recommended.

### CABINET OPENING DIMENSIONS


Cabinet opening dimensions shown are for 25" (64.0 cm) countertop depth, 24" (61.0 cm) base cabinet depth and 36" (91.4 cm) countertop height.

**IMPORTANT:** If installing a range hood or microwave hood combination above the range, following the range hood or microwave hoods combination instructions for dimensional clearances above the cooktop surface.

A freestanding range may be installed next to combustible walls with zero clearance.

\* **NOTE:** 24" (61.0 cm) minimum when bottom of wood or metal cabinet is covered by not less than  $\frac{1}{4}$ " (0.64 cm) flame retardant millboard covered with not less than No. 28 MSG sheet steel, 0.015" (0.4 mm) stainless steel, 0.024" (0.6 mm) aluminum or 0.020" (0.5 mm) copper.

### PRODUCT DIMENSIONS




- A. 27 $\frac{1}{4}$ " (70.5 cm) max. depth with handle
- B. 46 $\frac{1}{8}$ " (119.1 cm) overall height (max.) with leveling legs screwed all the way in\*
- C. 36" (91.4 cm) cooktop height (max.) with leveling legs screwed all the way in\*
- D. 29 $\frac{7}{8}$ " (75.9 cm) width
- E. 25 $\frac{5}{16}$ " (64.3 cm) depth – back of range to front of cooktop\*\*
- F. Model/serial rating plate (located on the left-side frame behind storage drawer or right side of frame behind the oven door)

**IMPORTANT:** Range must be level after installation. Follow the instructions in the "Level Range" section. Using the cooktop as a reference for leveling the range is not recommended.

\* Range can be raised approximately 1" (2.5 cm) by adjusting the leveling legs.

\*\* Front of door and drawer may extend further forward depending on styling.



- A. 13" (33.0 cm) max. upper cabinet depth
- B. 30" (76.2 cm) min. opening width
- C. For minimum clearance to top of cooktop, see NOTE\*
- D. 30 $\frac{1}{8}$ " (76.5 cm) min opening width
- E. Outlet – 8" (20.3 cm) to 22" (55.9 cm) from either cabinet, 5 $\frac{1}{2}$ " (14.0 cm) max. to floor
- F. Cabinet door or hinges should not extend into the cutout